



Teatro Cuyás

Las Palmas de Gran Canaria (España)

Arquitecto Architect

D. Luis Correa

Propietario Owner

CABILDO DE GRAN CANARIA

Contacto Contact

D. Gonzalo Angulo

Tlf. +34 928 365 080

Presupuesto Budget

1,9 millones de euros
1,9 millions of euros

ALCANCE

Ingeniería, fabricación, montaje y puesta en marcha del proyecto integral de equipamiento escénico para la Sala Principal y la Sala Petita, incluyendo:

	Cantidad
- Estructura de peine y galerías	SI
- Madera de suelo de escenario	SI
- Maquinaria Escénica y Textiles:	
• Telón Cortafuegos	1
• Barras contrapesadas	34
• Barras motorizadas	21
• Control de motores	1
• Barras manuales	6
• Motores puntuales	8
• Cámara de conciertos modular	1
• Telón de embocadura y bambalín	SI
• Cámara negra	SI
• Plataformas de foso de Orquesta	2
- Iluminación Profesional:	
• Mesa de control de iluminación	1
• Canales de dimmers	252
• Patch pannel de señal	SI
• Proyectoros	160
- Sonido Escénico:	
• Consola de mezclas	1
• Altavoces (monitores + P.A.)	22
• Reproductores / grabadores audio	4
• Micrófonos	28
• Intercomunicadores	6
- Videoproyección y conferencia:	
• Reproductores / grabadores vídeo	2
• Pantallas	1
• Vídeo Cámaras	2
• Sistemas de enrutamiento señal vídeo	SI
• Conferencias	SI
- Instalaciones Eléctricas:	
• Cuadros de protección	SI
• Cableados de fuerza y señal	SI
• Cajas de distribución de iluminación	SI
• Luz de trabajo	SI

SCOPE

Engineering, manufacturing, installation and commissioning of the global stage equipment contract for the main hall and the rehearsal halls, including:

	Quantity
- Steel works for grid and catwalks	YES
- Technical stage floor	YES
- Stage Machinery & Drapes:	
• Fire Safety Curtain	1
• Counterweight Flying Bars	34
• Motorised Flying Bars	21
• Hoist Control System	1
• Manual Rigging – Poles & Ropes-	6
• Chain/Cable Point Hoist	8
• Acoustic Shell	1
• House Curtain & border	YES
• Black Borders and Legs Sets	YES
• Orchestra Lifts	2
- Production Lighting:	
• Lighting control console	1
• Dimmer channels	252
• DMX-Ethernet patch	YES
• Luminaires	160
- Professional Audio System:	
• Audio mixing console	1
• Speakers+Monitoring	22
• Play/rec audio devices	4
• Microphones	28
• Intercom system stations	6
- Video and conference systems	
• Play/ rec video devices	2
• Screens	1
• Video Cameras	2
• Video Routing System	YES
• Conference system, simultaneous interpretation	YES
- Electrical Works:	
• Main Protection Boxes	YES
• Power & data cable	YES
• Production lighting Boxes	YES
• Work Lighting System	YES